



THE MUNICIPALITY OF SOUTHWEST MIDDLESEX  
REQUEST FOR TENDER: 2025-01  
LIMERICK LANDFILL CLOSURE,  
FINAL COVER AND STORMWATER DRAINAGE WORKS

**SEALED TENDERS**, in envelopes clearly marked as to the contents and showing the bidder's company name, will be received by:  
NAME, TITLE TBD, The Municipality of Southwest Middlesex, 153 McKeller Street, Glencoe, Ontario N0L 1M0.

The Tender closing date is **Wednesday, November 27, 2024, at 12:00 noon** local time.

Those interested in bidding are requested to attend a mandatory meeting on site on the following date: **Thursday, November 7, 2024, at 10:00 a.m.** local time, at the Limerick Landfill, located at 724 Limerick Road, Bothwell, Ontario. **Bids will not be opened from any company who did not have a representative at the mandatory site meeting.**

Please direct any questions or concerns pertaining to the tender to:

WSP Canada Inc., Fabiano Gondim, P. Eng., Senior Waste Engineer, Email: [Fabiano.Gondim@wsp.com](mailto:Fabiano.Gondim@wsp.com)

Questions accepted up until **Thursday, November 21, 2024, by 5:00 pm**, local time.

The work consists of the following major items (please refer to the Tender Document Sections 1.0 and 4.0 for detailed scope of work and estimated quantities:

1. Clear and grub vegetation within the construction areas located within inferred limit of waste and extents of the proposed perimeter ditches.
2. Strip and temporarily stockpile topsoil within the construction areas.
3. Regrade the landfill within the inferred waste limit to the top of waste lines and grades.
4. Realign, regrade and construct West Ditch 1 & 2, South Ditch 1 and East Ditch 1, 2 & 3 to the lines and grades shown on the Construction Drawings.
5. Supply and place rip rap aprons, complete with geotextile, within the ditches. Supply and install 300 mm diameter corrugated steel pipe (CSP) culvert, complete with a 100 mm diameter orifice plate as shown on the Construction Drawings, including frost protection, bedding, cover and associated works.
6. Supply, place, compact and grade the 600 mm thick clayey cover soil over the re-graded top of waste or soil fill. Place and grade 150 mm thick topsoil, obtained from on-Site temporary stockpiles, over the clayey cover soil.
7. Remove and dispose of the gate located at the existing north entrance along Limerick Road and replace it with fence panels. Install a new access gate and access road at the existing south Site entrance along Limerick Road.
8. Supply and place Seed Mix #1, nurse crop, mulch and fertilizer over the topsoil located within the inferred landfill limits. Supply and place Seed Mix #2, nurse crop, mulch and fertilizer over the topsoil located within the perimeter ditches.

Each tender must be accompanied by a tender deposit in the form of a certified cheque or Bid Bond as per the tender requirements, along with a signed Agreement to Bond for 100% Performance, 50% Labour and Material Payment and Maintenance Bond.

Tender documents, including maps, can be found on the Municipality's website at:

[www.southwestmiddlesex.ca](http://www.southwestmiddlesex.ca)

AutoCAD versions of drawings are available upon request.

Lowest or any tender will not necessary be accepted and is conditional upon acceptance of the Municipality of Southwest Middlesex.

Unit 10  
900 Maple Grove Road  
Cambridge, ON  
Canada N3H 4R7

T: +1-548-255-4055  
[wsp.com](http://wsp.com)